## **Estimate**

Audrey 917-679-0223 email: Woooac@gmail.com

Date 5/24/2010

Estimate #

|   |   | Terms   | Project   |
|---|---|---|---|
| Item  | Description   | Cost  | Total   |
| Labor<br>Labor<br>Labor<br>Labor<br>Air Scrubbers<br>Labor<br>Micro-Ban | 604 Granite/Cobblestone Unit 201-1<br>Remove all bat insulation from attic and replace with R38 blown in<br>insulation<br>Install vent in attic<br>Install planks to walk on during work<br>Set up negative air to vent while working<br>Run air scrubber in living space during work<br>Clean mold off of areas of wood sheeting and trusses<br>Apply anti-microbial to all affected areas of sheeting and trusses | 0.00<br>2,800.00<br>200.00<br>50.00<br>375.00<br>3,800.00<br>250.00 | 0.00<br>2,800.00<br>200.00<br>50.00<br>375.00<br>3,800.00<br>250.00 |
|   |   | Total   | \$7,525.00  |